BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK: Construction Of RCC Drians At Kuvempu School Road Mallasandra In Ward No.13, Shettyhalli Sub Division

SI No	Description Of Work	Unit	Qty	Rate To Be Quoted	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	KSRRB M300-14 Exavation For Road Work In All types of soil with hydraulic exavator of .9 cum bucket capacity including cutting and laoding in tippers,trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections,and transporting to the embankment location to a lead of 4.00km and complete asper specification Morth specification No.301 Page No.143, Item No.19.14 / PWD SR.2016-17	Cum	270.00	131.69	One hundred thirty One Rupees And Sixty nine Paisa Only
2	Removing B S Slab Drain And Stacking Page No25 Item No 5.32 PWD SR 2016-17	Sqm	837.00	65.72	Sixty Five Rupees and Seventy Two paisa Only
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 Page No.12/ Item No. 4.3/ PWD SR 2016-17	Cum	Available Course Aggregate		Four Thousand Four Hundred Forty Three Rupees And Fifty Two Paisa Only
			30.97	4443.52	
		Cum	Remaining Balance Qty		Five Thousand One Hundred Fifty Nine Rupees And Two Paisa Only
			14.54	5159.02	
4	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Page No.12/ Item No. 4.5/ PWD SR 2016-17	Cum	115.50	5874.52	Five Thousand Eight Hundred Seventy Four Rupees And Fifty Two Paisa Only
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.15/ Item No. 4.31/ PWD SR 2016-17	Sqm	1040.40	310.58	Three Hundred Ten Rupees And Fifty Eighty Paisa Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17	Tones	7.07	74331.44	Seventy Four thousand Three Thirty One Rupees And Forty Four Paisa Only
7	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	292.68	1680.00	One Thousand Six hundred Eighty Rupees Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature Of the Contractor

Executive Engineer,
Dasarahalli Division,